



T 7 S R 46 E

SECTIONS 16, 20, 21 & 28

BASIS OF BEARING

SOLAR OBSERVATIONS
8-25-81 & 9-21-81

MEAN MAGNETIC DECLINATION

N 20° 00' E

SURVEY HISTORY

THE SUBDIVISIONS OF T 7 S, R 46 E, W.M. WERE SURVEYED BY W.B. BARR, UNDER G.L.O. CONTRACT NUMBER 443, FROM AUGUST 16, TO SEPTEMBER 1, 1882. HANLEY ENGINEERING SURVEYED THE SOUTH SECTION LINE AND THE SOUTH HALF OF THE EAST SECTION LINE OF SECTION 16, DURING MAY AND JUNE, 1974. IN 1978 AND 1979 THEY SURVEYED THE EAST SECTION LINE, SOUTH SECTION LINE AND THE SOUTH HALF OF THE WEST SECTION LINE OF SECTION 28. IN 1979 THEY SURVEYED THE EAST SECTION LINES OF SECTIONS 16, 21 AND 28, WHILE SURVEYING THE SCATTER-DRY CADASTRAL SURVEY FOR U.S.F.S. JAMES HAMBLETON SURVEYED THE WEST SECTION LINE OF SECTION 20, DURING 1980 AND 1981, WHILE SURVEYING THE DIXIE CADASTRAL SURVEY FOR THE U.S.F.S.

NARRATIVE

SURVEY PERFORMED FOR THE U.S.F.S. UNDER STANDARD FOREST SERVICE CONTRACT. THE CONTRACT CONSISTED OF MONUMENTING FOUND CORNERS, BRINGING PREVIOUSLY MONUMENTED CORNERS UP TO STANDARD, LOCATING AND MONUMENTING LOST CORNERS BY SURVEY, SUBDIVIDING FOUR SECTIONS AND POSTING PROPERTY LINES BETWEEN U.S.F.S. LANDS AND OTHER OWNERSHIP. THREE 1/4 CORNERS AND ONE 1/16 CORNER WERE THE ONLY CONTROLLING CORNERS FOR THE FOUR SECTIONS THAT WERE MISSING. THESE WERE RE ESTABLISHED BY SURVEY AFTER A DILIGENT SEARCH WAS MADE FOR THEM. THE FOUR SECTIONS WERE SUBDIVIDED BY THE NORMAL METHOD TO ESTABLISH THE CENTER 1/4 CORNERS, 1/16 CORNERS AND 1/64 CORNERS AS SHOWN. A THREE MAN CREW WAS USED WITH A ONE SECOND THEODOLITE AND MAC II-H EDM. ALL OF THE SURVEYS WERE CLOSED LOOP TRAVERSES.

I, BARRY B. BARBOUR, a registered land surveyor in the State of Oregon, hereby certify that this plat and the notes hereon, or attached, are a correct representation of a survey I performed during August, September, and October, 1981, for the U.S. Forest Service in accordance with the Statutes of the State of Oregon and with the Articles of the Contract.

Barry B. Barbour
Barry B. Barbour
Registered Land Surveyor
Oregon License 1051

LEGEND

- FOUND MONUMENT OF RECORD
- ▲ FOUND MONUMENT OF RECORD, REPLACED DOME CAP WITH BRASS CAP
- FOUND 5/8" REBAR AND PLASTIC CAP OF RECORD SURVEY
- FOUND ORIGINAL CORNER EVIDENCE AND SET MONUMENT AS DESCRIBED ON ATTACHED U.S.F.S. R6-7100-57.
- ⊕ SET MONUMENT FROM SURVEY AS DESCRIBED ON ATTACHED U.S.F.S. R6-7100-57.
- () RECORD G.L.O. DATA
- * RECORD SURVEY 7-46-1 OR 7-46-13-A OR 7-46-73 OR 7-46-74.
- # RECORD SURVEY 7-45-75
- [] METERS
- POSTED BOUNDARY LINES

REFERENCE MATERIAL

ORIGINAL G.L.O. NOTES AND PLAT
FIELD BOOKS 1-7
SURVEYS: 7-46-1
7-46-13-A
7-46-73
7-46-74
7-45-75

NOTE

FORM R6-7100-57 FILED AT BAKER COUNTY SURVEYORS FOR THE STANDARD INDEX FILE NUMBERS: 21-9, J-11, L-9, L-11, M-11, M-N-10, M-N-11, N-7, N-8, N-9, N-10, N-11, N-12, O-8, O-9, O-11, O-12, P-7, P-9, P-11, P-12, Q-12, R-7, R-9, R-11, R-12, S-12, S-13, T-11 AND V-11.

REGISTERED PROFESSIONAL LAND SURVEYOR

Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

SCALE:
FEET 0 1000 2000
METERS 0 304.80m 609.60m
METER CONVERSION 3.280833333 ft./m.

FILED Jan 25, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-95

CONTRACT NO. 53-04M3-1-2686N

BEECHER CADASTRAL		
SECTIONS 16, 20, 21 & 28		
BAKER COUNTY, OREGON		
U.S.F.S. WALLOWA-WHITMAN NATIONAL FOREST		
SCALE: 1" = 1000'	BARRY B. BARBOUR PROFESSIONAL LAND SURVEYOR	SHEET NO. 1
DATE: DEC, 1981	P.O. BOX 833 BAKER, OREGON	