


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. A-9

History of original corner establishment:

Corner was originally established under G.L.O. contract No. 443 by W. B. Barr; during July of 1882. Surveyors General's notes state: "Set granite boulder 12 x 9 x 8 ins. 8 inches in ground for corner to sec. 4, 5, 32, 33, marked with 4 notches on the East and 2 notches on the West sides from which: a tamarack 17 in. diam. bears N35°E, 70 lks. dist. marked T6SR46E S33 BT. A spruce 15 in. diam. bears N37°W, 12 lks. dist. marked T6SR46E S32 BT. A fir 6 in. diam. bears S69°W 6 lks. dist. marked T7SR46E S5 BT. A tamarack 14 in. diam. bears S37°E, 58 lks. dist. marked T7SR46E S4 BT."



Description of corner evidence found:

Found 12 x 11 x 7 inch stone firmly set with 4 notches on East side. From which: a 38" tamarac bears N35°E, 45.0 ft. with almost grown over blaze. A 24" rotten stump bears S35°E, 36.3 ft. A 28" fir bears S75°W, 5.0 ft. A rotten stump bears N40°W, 8 ft.

Description of monument and accessories established to perpetuate the original location of this corner:

At center of set stone set 2 1/2" x 30" galvanized pipe and brass cap marked; Set pipe 24" in the ground and mound of stone around to cap. Placed marked stone alongside. From which by magnetic declination of N20°E: A 22" fir bears S17°E, 63.9 ft. scribed T7SR46E S4 BT. An 18" fir bears N44°W, 91.5 ft. scribed T6SR46E S32 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-4s, and brass washers stamped PLS 1051 on BTs. Old BTs are signed. Placed 54-4 on a steel fence post 5' North of the corner.

T6S R46E
S32 S33
 +
S5 S4
 T7S
OR PLS 1051
1981

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Dave Poe

October 16, 1981

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of..... Baker.....
State of..... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the... 25... day of... January....., 1982
..... County Surveyor..... by..... Tom H. Hensley.....
(COUNTY OFFICIAL) (DEPUTY)

FILED Jan. 25, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-98