

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. A-19

History of original corner establishment:

Corner was originally established under G.L.O. contract No. 443 by W. B. Barr, during July of 1882. Surveyors General's notes state: "Set basalt rock 12 x 10 x 9 ins. 8 inches in ground for 1/4 sec. corner marked 1/4 on the North side from which: a fir 6 in. diam. bears N17°W, 144 lks. dist. marked 1/4 S. BT. A pine 15 in. diam. bears S17°E, 196 lks. dist. marked 1/4 S. BT."

DIAGRAM

T6S R46E
S35
1/4 —
S2
T7S

Description of corner evidence found:

Found no trace of record stone or North BT. Found 16" pine snag with scribed BT. Measured N17°W, 129.4 ft.

Description of monument and accessories I established to perpetuate the original location of this corner:

At measured point set 2 1/2" x 30" galvanized pipe and brass cap marked:
Set pipe 12" in the ground to bedrock and mound of stone around to cap.
From which by magnetic declination of N20°E:
A 26" fir bears N49°E, 81.5 ft. scribed 1/4 S35 BT.
A 14" pine bears S38°W, 101.3 ft. scribed 1/4 S2 BT.
Painted blazes red and 6" red band around. Placed 54-3s, 54-4s, and brass washers stamped PLS 1051 on BTs. Placed 54-4 on a steel fence post 5' West of the corner.
Corner falls on North slope of East-West ridge.

T6S R46E
S35
1/4 —
S2
T7S
OR PLS 1051
1981

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Dave Poe

October 21, 1981

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour
**OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051**