

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. E-17

History of original corner establishment:

Corner was originally established under G.L.O. contract No. 443 by W. B. Barr, during August of 1882. Surveyors General's notes state: "Set basalt rock 13 x 10 x 8 ins. 9 inches in the ground for corner to Sec. 2, 3, 10, 11, marked with 2 notches on the East and 5 notches on the South edges from which: A pine 40 in. diam. bears N11°E, 14 lks. dist. marked T7SR46E S2 BT. A pine 5 in. diam. bears N85°W, 74 lks. dist. marked T7SR46E S3 BT. A pine 12 in. diam. bears S21°W, 37 lks. dist. marked T7SR46E S10 BT. A fir 5 in. diam. bears S32°E, 26 lks. dist. marked T7SR46E S11 BT."

DIAGRAM

T7S R46E
S3 | S2
—+—
S10 | S11

Description of corner evidence found:

Found no trace of recorded stone. Found opened 30" pine with visible scribing. Measured S11°W, from 40" pine stump, 9.2 ft. From here rotten pine stump bears S26°W, 24.6 ft. and opened tree bears N84°W, 52.1 ft.

Description of monument and accessories established to perpetuate the original location of this corner:

At measured point set 2 1/2" x 30" galvanized pipe and brass cap marked:
Set pipe 25" in the ground.
From which by magnetic declination of N20°E:
A 12" fir bears N22°E, 31.5 ft. scribed T7SR46E S2 BT.
A 16" pine bears S28°E, 7.5 ft. scribed T7SR46E S11 BT.
A 15" fir bears S86°W, 44.0 ft. scribed T7SR46E S10 BT.
A 12" pine bears N41°W, 43.4 ft. scribed T7SR46E S3 BT.
Painted blazes red and 6" red band around. Placed 54-3s, 54-4s, and brass washers stamped PLS 1051 on BTs. Placed 54-4 on a steel fence post 5' West of the corner.

T7S R46E
S3 | S2
—+—
S10 | S11
OR PLS 1051
1981

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Dave Poe

October 20, 1981

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour
**OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051**

Office of _____ County Surveyor _____ County of _____ Baker
State of _____ Oregon _____, I hereby certify that the within instrument was filed in this office
for record on the _____ 7.5. day of _____ January _____, 1982.
_____ County Surveyor _____ by _____ *Tara Hawley*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

★ GPO—798-276

FILED Jan. 25, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-108