

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. E-25

History of original corner establishment:

Corner was originally established under G.L.O. contract No. 443 by W. B. Barr, during July of 1882. Surveyors General's notes state: "Set basalt rock 16 x 12 x 9 ins. 11 inches in ground for corner to sec. 1, 6, 7, 12, marked with 1 notch on the North and 5 notches on the South sides, from which: A pine 6 in. diam. bears N75°E, 43 lks. dist. marked T7SR47E S6 BT. A pine 6 in. diam. bears N66°W, 43 lks. dist. marked T7SR46E S1 BT. A pine 36 in. diam. bears S18°W, 57 lks. dist. marked T7SR46E S12 BT. A cottenwood 4 in. diam. bears S40°E, 23 lks. dist. marked T7SR47E S7 BT."

DIAGRAM

T7S
R46E R47E
S1 S6
S12 S7

Description of corner evidence found:

Found firmly set 16 x 12 x 9 inch stone with 5 notches on South edge and 1 notch on North edge. From which: A 36" pine stump bears N72°E, 28.3 28.6 ft. with visible scribing. A 36" down pine bears S16°W, 37.6 ft. with visible scribing. A 36" pine stump bears N68°W, 29.4 ft. with no visible scribing.

Description of monument and accessories I established to perpetuate the original location of this corner:

At center of the above stone set 2 1/2" x 30" galvanized pipe and brass cap marked:
Set pipe 25" in the ground, and placed marked stone alongside.
From which by magnetic declination of N20°E:
A 12" pine bears N21°E, 34.3 ft. scribed T7SR47E S6 BT.
A 15" pine bears S27°E, 89.4 ft. scribed T7SR47E S7 BT.
A 12" pine bears S30°W, 47.0 ft. scribed T7SR46E S12 BT.
An 18" pine bears N05°W, 44.5 ft. scribed T7SR46E S1 BT.
Painted blazes red and 6" red band around. Placed 54-3s, 54-4s, and brass washers stamped PLS 1051 on BTs. Placed 54-4 on a steel fence post 5' West of the corner.

T7S
R46E R47E
S1 S6
S12 S7
OR PLS 1051
1981

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Dave Poe

October 20, 1981

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of..... County Surveyor..... County of Baker.....
State of..... Oregon..... ; I hereby certify that the within instrument was filed in this office
for record on the... 7... day of..... January..... 1982
..... County Surveyor..... by..... Tom Hanley.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Jan. 25, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-110