


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. G-21

History of original corner establishment:

Corner was originally established under G.L.O. contract No. 443 by W. B. Barr, during August of 1882. Surveyors General's notes state: "Set volcanic rock 12 x 9 x 7 ins. 8 inches in ground for 1/4 Sec. corner marked 1/4 on the West side, from which: A pine 25 in. diam. bears S69°W, 165 lks. dist. marked 1/4 S. B.T. A pine 20 in. diam. bears N10°E, 36 lks. dist. marked 1/4 S. B.T."



Description of corner evidence found:

Found no trace of record stone. Found rotten pine stump with BT scribe left. Measured S10°W, 23.7 ft. From here a down and rotten pine with no scribing left bears S67°W, 110 ft. to approximate stump hole.

Description of monument and accessories established to perpetuate the original location of this corner:

At measured point set 2 1/2" x 30" galvanized pipe and brass cap marked:
Set pipe 24" in the ground.
From which by magnetic declination of N20°E:
A 20" pine bears N78°E, 41.5 ft. scribed 1/4 S12 BT.
An 18" pine bears N77°W, 22.0 ft. scribed 1/4 S11 BT.
Painted blazes red and 6" red band around. Placed 54-3s, 54-4s, and brass washers stamped PLS 1051 on BTs. Old BTs are signed. Placed 54-4 on a steel fence post 5' North of the corner. Corner falls at head of gulch near large flat area on ridge.

T7S R46E
1/4
S11 + S12
OR PLS 1051
1981

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Dave Poe

October 21, 1981

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor..... County of..... Baker.....
State of..... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the... 25... day of... January....., 1982
..... County Surveyor..... by..... Tom Henley.....
(COUNTY OFFICIAL) (DEPUTY)

FILED Jan. 25, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 7-46-114