

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-17

History of original corner establishment:

Corner was originally established under G.L.O. contract No. 443 by W. B. Barr, during August, 1882. Surveyors General's notes state: "Set basalt rock 17 x 11 x 17 ins. 12 inches in ground for corner to Sec. 10, 11, 14, 15 marked with 4 notches on the South and 2 notches on the East edges from which: A pine 36 ins. dia. bears N57°E., 128 lks. dist. marked T7SR46ES11 BT. A pine 24" diam bears N13°W., 38 lks. dist. marked T3SR46ES10 BT. A 24" pine bears S17°W., 80 lks. dist. marked T7SR46ES15 BT. A 36" pine bears S46°E., 266 lks. dist. marked T7SR46ES14 BT."

DIAGRAM

T7SR46E
S10 | S11
+
S15 | S14

Description of corner evidence found:

Found no trace of record stone or NE BT.
Found 26" down pine with visible scribing. Measured N17°E., 52.8 ft. and found 2" hub. N13°W about 24 ft. is rotten pine stump. S45°E., 173 ft. is a rotten stump in place.

Description of monument and accessories established to perpetuate the original location of this corner:

At measured point set 2 1/2" x 30" galvanized pipe and brass cap marked: Set pipe 12" in the ground and mound of stone around to cap.

From which by magnetic declination on N20°E:

A 18" pine bears N85°E., 19.4 ft. scribed T7SR46ES11 BT.

A 16" pine bears S21°E., 67.8 ft. scribed T7SR46ES14 BT.

A 12" pine bears S83°W., 22.3 ft. scribed T7SR46ES15 BT.

A 16" pine bears N59°W., 12.9 ft. scribed T7SR46ES10 BT.

Painted blazes red and 6" red band around. Placed 54-3s, and 54-4s and brass washers stamped PLS 1051 on BT. Placed 54-4 on a steel fence post 5' south of the corner

T7SR46E
S10 | S11
+
S15 | S14
OR PLS 1051
1981

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Dave Poe

August 19, 1981