


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Index File No. M-N-10

History of original corner establishment:

None




Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" x 30" galvanized pipe and brass cap marked: Set pipe 25" in the ground. No rock in area. From which by magnetic declination of N20°E;  
 A 12" pine bears S53 1/2°W., 34.3 ft. scribed SWCSS1/64S16 BT  
 A 24" pine bears N28°W., 60.5 ft. scribed SWCSS1/64S16 BT.  
 Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on the BT. Placed 54-2 and 54-9 on a steel fence post 5' east and 54-2 on a steel fence post 5' south of the corner.



I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel Rowland  
 Dave Poe

September 8, 1981

**REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR**

*Barry B. Barbour*

OREGON  
 OCT. 17, 1975  
**BARRY B. BARBOUR**  
 1031

Office of...County Surveyor..... County of.....Baker.....  
 State of.....Oregon..... I hereby certify that the within instrument was filed in this office  
 for record on the 25 day of January, 1982  
 County Surveyor by Tom Hawley  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED Jan. 25, 1982  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 7-46-122