


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. N-12

History of original corner establishment:



Description of corner evidence found:

Found 2 1/2" x 15" pipe with aluminum dome cap about 0.35 ft. from computed position.

Description of monument and accessories I established to perpetuate the original location of this corner:


At center of above point pulled aluminum cap and replaced it with brass cap stamped: Pipe projects 15" above ground, Encased in concrete. Built mound of stone around to cap. Heavy brush along creek prevents using BT in North quadrants. From which by magnetic declination of N20°E:
 A 22" fir bears S43 1/2°E., 92.8 ft. scribed E1/16S21 BT.
 A 24" fir bears S34°W., 81.6 ft. scribed E1/16S21 BT.
 Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on the BT. Placed 54-2 and 54-9 on a steel fence post 5' east and 54-2 on a steel fence post 5' south of the corner.

T7SR46E
S16
E ——— 1/16
S21
OR PLS 1051
1981

I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel Rowland
Dave Poe

September 8, 1981



Barry B. Barbour
 OREGON
 OCT. 17, 1975
 BARRY B. BARBOUR
 1031

Office of County Surveyor..... County of... Baker.....
 State of... Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the... 25... day of... January....., 19... 82
 County Surveyor..... by Tom Hanley.....
 (COUNTY OFFICIAL) (DEPUTY)

FILED Jan 25, 1982
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-46-128