

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. 0-9

History of original corner establishment:

No history.

DIAGRAM

T7S R46E  
N 1/16  
S20 + S21

Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" x 30" galvanized pipe and brass cap marked:  
Set pipe 24" in the ground and mound of stone around to cap.  
From which by T-2 and EDM:  
An 18" pine bears N26°E, 409.6 ft. scribed N 1/16 S21 BT.  
A 16" pine bears N19°W, 324.7 ft. scribed N 1/16 S20 BT.  
Painted blazes red and 6" red band around. Placed 54-3s, 54-9s, and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on a steel fence post 5' East and 54-2 on a steel fence post 5' West of the corner.  
Corner falls in large meadow about 100' North of East Fork of Pine Creek.

T7S R46E  
N 1/16  
S20 + S21  
OR PLS 1051  
1981

I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel Rowland  
Dave Poe

September 29, 1981

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Barry B. Barbour*

OREGON  
OCT. 17, 1975  
BARRY B. BARBOUR  
1051

Office of County Surveyor County of Baker  
State of Oregon I hereby certify that the within instrument was filed in this office  
for record on the 25 day of January, 1982  
Barry B. Barbour by Tara Handley  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RGPO-798-276

FILED Jan 25, 1982  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-46-130