


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Index File No. 0-11

**History of original corner establishment:**

No history.



**Description of corner evidence found:**

None.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At surveyed point set 2 1/2" x 30" galvanized pipe and brass cap marked;  
 Set pipe 25" in the ground. No rock in the area.  
 From which by T-2 and EDM;  
 A 15" fir bears S26°E, 47.2 ft. scribed CN 1/16 S21 BT.  
 A 16" fir bears S85 1/2°W, 67.2 ft. scribed CN 1/16 S21 BT.  
 Painted blazes red and 6" red band around. Placed 54-3s, 54-9s, and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on a steel fence post 5' East and 54-2 on a steel fence post 5' West of the corner.

T7S R46E  
 C  
 N 1/16 —+— S21  
 C  
 OR PLS 1051  
 1981

I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel Rowland  
Dave Poe

August 29, 1981

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Barry B. Barbour*

OREGON  
 OCT. 17, 1973  
 BARRY B. BARBOUR  
 1051

Office of...County...Surveyor..... County of...Baker.....  
 State of...Oregon..... I hereby certify that the within instrument was filed in this office  
 for record on the...25...day of...January....., 1982.

.....County...Supt..... by .....*Tara Hendry*.....  
 (COUNTY OFFICIAL) (DEPUTY)