


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Index File No. 0-12

**History of original corner establishment:**

No history.

**DIAGRAM**




**Description of corner evidence found:**

None.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At surveyed point set 2 1/2" x 30" galvanized pipe and brass cap marked:  
 Set pipe 25" in the ground and mound of stone around to cap.  
 From which by magnetic declination of N20°E;  
 A 16" fir bears S73°E, 5.9 ft. scribed NE 1/16 S21 BT.  
 An 11" fir bears N79°W, 24.0 ft. scribed NE 1/16 S21 BT.  
 Painted blazes red and 6" red band around. Placed 54-3s, 54-9s, and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on a steel fence post 5' North and a 54-2 on a steel fence post 5' West of the corner.



I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel Rowland  
Dave Poe

October 8, 1981

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Barry B. Barbour*

OREGON  
OCT. 17, 1975  
BARRY D. BARBOUR  
1031

Office of.....County Surveyor..... County of.....Baker.....

State of.....Oregon..... I hereby certify that the within instrument was filed in this office for record on the...25... day of.....January....., 1982

.....County Surveyor..... by.....Tom Hamby.....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

GPO-798-276

FILED Jan. 25, 1982  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 7-46-132