


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. P-11

History of original corner establishment:

No history.



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" x 30" galvanized pipe and brass cap marked; Set pipe 26" in the ground. From which by magnetic declination of N20°E: An 11" fir bears N76°E, 14.0 ft. scribed C 1/4 S21 BT. A 15" fir bears N47°W, 38.4 ft. scribed C 1/4 S21 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s, and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on a steel fence post 5' East and 54-2 on a steel fence post 5' South of the corner.

T7S R46E C 1/4 S21 OR-PLS 1051 1981

I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel Rowland Dave Poe

October 6, 1981

REGISTERED PROFESSIONAL LAND SURVEYOR

Barry B. Barbour

OREGON OCT. 17, 1975 BARRY B. BARBOUR 1051

Office of...County Surveyor... County of...Baker...

State of...Oregon... I hereby certify that the within instrument was filed in this office

for record on the 75 day of January, 1982

County Surveyor by Tom Handley (DEPUTY)