


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Index File No. 0-12

**History of original corner establishment:**

No history.



**Description of corner evidence found:**

None.

**Description of monument and accessories established to perpetuate the original location of this corner:**

T7S R46E  
SE  
1/16

OR PLS 1051  
1981

At surveyed point set 2 1/2" x 30" galvanized pipe and brass cap marked;  
Set pipe 26" in the ground.  
From which by magnetic declination of N20°E;  
A 16" pine bears N54°E, 21.3 ft. scribed SE 1/16 S21 BT.  
A 16" pine bears S49°W, 23.8 ft. scribed SE 1/16 S21 BT.  
Painted blazes red and 6" red band around. Placed 54-3s, 54-9s, and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on a steel fence post 5' East and a 54-2 on a steel fence post 5' North of the corner.

I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel Rowland  
Dave Poe

October 7, 1981

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*Barry B. Barbour*

**OREGON  
OCT. 17, 1975  
BARRY B. BARBOUR  
1051**

Office of.....County Surveyor..... County of..Baker.....  
State of...Oregon..... I hereby certify that the within instrument was filed in this office  
for record on the...25... day of...January....., 1982.  
.....County Surveyor..... by .....Tom Hendley.....  
(COUNTY OFFICIAL) (DEPUTY)

FILED Jan 25, 1982  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-46-137