

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. R-11

History of original corner establishment:

Corner was originally established under G. L. O. contract No. 443 by W. B. Barr, during August, 1882. Surveyors General's notes state: "Set volcanic rock 22 X 18 X 14 for 1/4 Sec. corner 17 inches in the ground marked 1/4 on the north side. From which: A pine 9 ins. diam. bears N41°W, 23 lks. dist. marked 1/4S BT. A pine 12 ins. diam. bears S24°E, 46 lks. dist. marked 1/4S BT."

DIAGRAM

T7S R46E
1/4 $\frac{S21}{S28}$

Description of corner evidence found:

Found aluminum pipe and cap marked: From which an 18" Pine bears N49°W, 14.6 ft. with grown over blazes. A 15' high, 20" Pine snag bears S19°E, 31.5 ft. with visible 1/4S BT scribing.

T7S R46E
S21
1/4 $\frac{S21}{S28}$
S28
CS 1974

Description of monument and accessories I established to perpetuate the original location of this corner:

From which by magnetic declination of N20°E, I add: An 18" Fir bears S32°W, 69.5 ft. scribed 1/4 S28 BT. Painted blazes red and 6" red band around. Placed 54-3, 54-4 and brass washer stamped PLS 1051 on the BT. Placed 54-3s, 54-4s and painted the old BTs. Placed 54-2 and 54-4 on a steel fence post 5' north and placed 54-2 on a steel fence post 5' east, south and west of the corner.

I hereby certify that the above work was performed to perpetuate the found monument.

Witnesses: Daniel Rowland
Dave Poe

September 15, 1981

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour
OREGON
OCT. 17, 1973
BARRY B. BARBOUR
1031

Office of..... County Surveyor..... County of..... Baker.....
State of..... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the... 25... day of..... January....., 1982
..... County Surveyor..... by..... Tom Hanley.....
(COUNTY OFFICIAL) (DEPUTY)

FILED Jan. 25, 1982
BAKER COUNTY SURVEYOR
SER/RY NO. 7-46-139