

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Index File No. R-9

**History of original corner establishment:**

Corner was originally established under G.L.O. contract No. 443 by W. B. Barr, during August of 1882. Surveyors General's notes state: "Set volcanic rock 15 x 12 x 10 ins. 10 inches in the ground for corner to Sec. 20, 21, 28, 29, marked with 2 notches on the South and 4 notches on the East edges from which a pine 18 in. diam. bears N66°E, 160 lks. dist. marked T7SR46E S21 BT. No other trees within limits. Raised mound of rock alongside."

**DIAGRAM**

T7S	R46E
S20	S21
S29	S28

**Description of corner evidence found:**

Found 14 x 12 x 10 inch stone firmly set and marked with 2 notches on South and 4 notches on East sides. From which: A 30" pine bears N66°E, 105.6 ft. with open blaze and visible scribing. Mound of stone West of marked stone.

**Description of monument and accessories established to perpetuate the original location of this corner:**

At center of the above stone set 2 1/2" x 30" galvanized pipe and brass cap marked:  
 Set pipe 25" in the ground and mound of stone around to cap. Placed marked stone alongside.  
 From which by magnetic declination of N20°E:  
 A 30" pine bears N87°W, 102.3 ft. scribed T7SR46E S20 BT. No other trees within limits. Painted blazes red and 6" red band around. Placed 54-3, 54-4, and brass washer stamped PLS 1051 on BT. Painted old BT and placed 54-3 and 54-4. Re-built mound of stone 5' West of the corner. Placed 54-2 and 54-4 on a steel fence post 5' East and 54-2 on a steel fence post 3' West of the corner.

T7S	R46E
S20	S21
S29	S28

OR PLS 1051  
1981

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland  
Dave Poe

September 10, 1981

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*Barry B. Barbour*  
**OREGON  
OCT. 17, 1975  
BARRY B. BARBOUR  
1031**

Office of.....County Surveyor..... County of.....Baker.....  
 State of.....Oregon..... I hereby certify that the within instrument was filed in this office  
 for record on the 15 day of.....January....., 1982  
 .....*Tom Hendley*..... by .....*Tom Hendley*.....  
 (COUNTY OFFICIAL) (DEPUTY)