

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

No history.

Index File No. S-12

DIAGRAM

T7S R46E
NE + S28
1/16

Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" x 30" galvanized pipe and brass cap marked;

Set pipe 12" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E:

A 12" pine bears S61°E, 198.2 ft. scribed NE 1/16 S28 BT.

A 14" pine bears N38°W, 196.6 ft. scribed NE 1/16 S28 BT.

Painted blazes red and 6" red band around. Placed 54-3s, 54-9s,

and brass washers stamped PLS 1051 on BTs. Placed 54-2 and

54-9 on a steel fence post 5' North and 54-2 on a steel fence post 5' East of the corner.

T7S R46E
NE + S28
1/16
OR PLS 1051
1981

I hereby certify that the above corner monument was established as herein described.

Witnesses: Daniel Rowland
Dave Poe

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1031