

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was originally established under GLO contract number 707, by Williard B. Blakeslee on June 9, 1901. Surveyor General's notes state: "Set a granite stone 16 x 12 x 6 ins., 10 ins. in the grn. for 1/4 sec. cor., marked 1/4S on the W. face from which a pine 10 ins. in diam. brs. N30°W. 60 lks. dist. marked 1/4 S3 BT and a pine 10 ins. in diam. brs. N75°E. 10 lks. dist., marked 1/4 S2 BT.

Index File No. C-17

**DIAGRAM**

T7S R47E

1/4

S 3 + S 2

Description of corner evidence found:

Found 16 x 10 x 6 inch stone, firmly set and clearly marked 1/4S on West face. From which a live 21" pine bears N75°E., 6.6 ft., with grown-over blazes. A 27" pine bears N50°W., 39.6 ft., with grown-over blazes.

Description of monument and accessories established to perpetuate the original location of this corner:

At the center of the above point, set 2 1/2" x 30" galvanized pipe and brass cap marked as shown. Set pipe 22" in the ground and mound of stone around to cap. Buried marked stone alongside of the pipe.

Painted blazes red and 6" red band around. Placed 54-3s and 54-4s on the BTs. Placed 54-4 on a steel fence post 5 ft. south of the corner.

T7S R47E

1/4

S 3 + S 2

OR PLS 1051

1981

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David Cummins  
Daniel Rowland  
Brian Cays

April 29, 1981

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Barry B. Barbour*

OREGON  
OCT. 17, 1975  
BARRY B. BARBOUR  
1051

Office of.....County Surveyor..... County of.....Baker.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office

for record on the.....day of.....June.....1981