


Index File No. N-7

History of original corner establishment:

Corner was originally established under G. L. O. contract number 707, by Williard B. Blakeslee on August 3, 1901. Surveyor General's notes state: "Set a granite stone 12 x 3 x 4 ins., 8 ins. in the ground for 1/4 sec. cor. marked 1/4 S on the N. face from which a pine tree 8 ins. in diam. brs., S10°W, 7 lks., dist. marked 1/4 S20 BT. and a fir 16 ins. in diam., brs. N10°E 10 lks. dist. marked 1/4 S17 BT."



Description of corner evidence found:

Found no trace of corner stone or BTs.  
 Opened 30" Fir found in 1980.  
 About 72 years ago this tree was burned, but no axe marks or scribing on old blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

At the center of surveyed point, set 2 1/2" x 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.  
 From which by magnetic declination of N20°E:  
 A 12" Fir bears N19°E., 9.4 ft. scribed 1/4 S17 BT.  
 A 15" Fir bears S24°E., 41.0 ft. scribed 1/4 S20 BT.  
 Painted blazes red and 6" red band around.  
 Placed 54-3s, 54-4s, and brass washers stamped PLS 1051 on the BTs.  
 Placed 54-4 on a steel fence post 5' east of the corner.

T7S R47E  
 S17  
 1/4 —+—  
 S20  
 OR PLS 1051  
 1981

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland  
 Douglas Moser

April 30, 1981

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Barry B. Barbour*  
 OREGON  
 OCT. 17, 1975  
 BARRY B. BARBOUR  
 1051

Office of.....County Surveyor..... County of.....Baker.....  
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 1981.  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

FILED Jun 1, 27, 1981  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 7-47-24