


History of original corner establishment:




Corner was originally established under G. L. O. contract number 707, by Williard B. Blakeslee on June 15, 1901. Surveyor General's notes state: "Set a basalt stone 14 X 8 X 6 ins., 8 ins. in the grnd. for the cor. to secs., 16, 17, 20, & 21, marked with 3 notches on the S. and 4 on the E. faces, raised a mound of stone 3 ft. base, 24 ins. high, 10 lks. W. of the cor. (Pits Imp.)."

Description of corner evidence found:

Found 18 X 8 X 8 inch stone set in a mound of stone, plainly marked with 4 notches on the east, and 3 notches on the south. Found possible remains of mound of stone 10 lks. west of the corner.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the center of the above point, set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap. Buried marked stone alongside of the pipe.




From which by magnetic declination of N20°E:
 A 10" pine bears N43°E, 33.2 ft. scribed T7S R47E S16 BT. A 19" fir bears S75°E, 95.9 ft. scribed T7S R47E S21 BT. A 42" pine bears S50°W, 143.6 ft. scribed T7S R47E S20 BT. A 12" pine bears N88°W, 126.4 ft. scribed T7S R47E S17 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS 1051 on the BT's. Placed 54-2 and 54-4 on a steel fence post 5' east and placed 54-2 on a steel fence post 5' north of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David Cummins
 Daniel Rowland
 Douglas Moser

January 27, 1981



Barry S. Banskour
 OREGON
 OCT. 17, 1975
 BARRY S. BANSKOUR
 1031

Office of...County Surveyor..... County of.....Baker.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 1981.
 by
 (COUNTY OFFICIAL) (DEPUTY)

FILED Jan 27, 1981
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-47-25