


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. 0-3

History of original corner establishment:




Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point, set 2 1/2" x 30" galvanized pipe and brass cap marked:
 Set pipe 24" in the ground and mound of stone around to cap.
 From which by magnetic declination of N20°E
 A 12" pine bears S50°E., 28.7 ft. scribed C N 1/16 S19 BT.
 A 8" fir bears N04°E., 23.5 ft. scribed CN 1/16 S19 BT.
 Painted blazes red and 6" red band around. Placed 54-3s, 54-9s, and brass washers stamped PLS 1051 on the BTs.
 Placed 54-2 and 54-9 on a steel fence post 5' North and placed 54-2 on a steel fence post 5' West of the corner.



I hereby certify that the above corner monument was established as herein described.

Witnesses: David Cummins
Douglas Moser
Brian Cays

April 24, 1981

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1031

Office of..... County Surveyor..... County of..... Baker.....
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... June....., 19..... 81
 by
 (COUNTY OFFICIAL) (DEPUTY)

FILED July 27, 1981
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-47-28