


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. 0-13

History of original corner establishment:

NOT SET



Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner:


At the center of the surveyed point, set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 20" in the ground and mound of stone around to cap.
 From which by magnetic declination N20°E:
 A 16" pine bears N65°W, 129.7 ft. scribed N1/16S21 BT.
 No other trees available.
 Painted blazes red and 6" red band around. Placed 54-3s, 54-9s, and brass washers stamped PLS 1051 on the BTs. Placed 54-2 and 54-9 on a steel fence post 5' south and placed 54-2 on a steel fence post 5' west of the corner, and raised a mound of stone 3 ft. base, 3 ft. high, 5 ft. east of corner.

T7S R47E
 N 1/16
 S21 + S22
 OR PLS 1051
 1981

I hereby certify that the above corner monument was established as herein described.

Witnesses: David Cummins
Daniel Rowland
Douglas Moser

February 23, 1981



Barry D. Barbour
 OREGON
 OCT. 17, 1975
 BARRY D. BARBOUR
 1051

Office of.....County Surveyor..... County of Baker.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 1981.

..... by *Thomas J. [Signature]* (DEPUTY)

(COUNTY OFFICIAL)

FILED July 27, 1981
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-47-30