


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. P-12

History of original corner establishment:

NOT SET



Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner:

At the center of the surveyed point, set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E:

A 26" pine bears N13°W., 137.5 ft. scribed CE1/16S21 BT.

A 16" pine bears S54°W., 164.4 ft. scribed CE1/16S21 BT.

Painted blazes red and 6" red band around. Placed 54-3s, 54-9s, and brass washers stamped PLS 1051 on the BT's. Placed 54-2, 54-9 on a steel fence post 5' south and placed 54-2 on a steel fence post 52 ft. north of the corner on ridge top.

T7S R47E
E1/16


C—+—C

S21
OR PLS 1051
1981

I hereby certify that the above corner monument was established as herein described.

Witnesses: David Cummins
Daniel Rowland
Douglas Moser

February 20, 1981



Barry B. Barbour
 OREGON
 OCT. 17, 1978
 BARRY B. BARBOUR
 1981

Office of... County Surveyor..... County of... Baker.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19⁸¹
 by *T. J. ...*
 (COUNTY OFFICIAL) (DEPUTY)

FILED *July 27, 1981*
 BAKER COUNTY SURVEYOR
 SURVEY NO. *7-47-36*