


History of original corner establishment:

Corner was originally established under G. L. O. contract number 707, by Williard B. Blakeslee on June 14, 1901. Surveyor General's notes state: "Set a basalt stone 16 X 12 X 10 ins., in the grd. for the cor. to sec. 20-21-28 & 29 marked with 2 notches on the S. and 4 notches on the E. faces, raised a md. of stone 3 ft. base, 24 inches high 10 lks. W. of the corner. (Imp Pits). "



Description of corner evidence found:

Found 16 X 12 X 6 inch stone set firmly in the ground with 4 notches N. and 2 notches W. (probably turned over once upon a time). Found definite mound of stone 10 lks. W.

Description of monument and accessories established to perpetuate the original location of this corner:


At the center of the above point, set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap. Buried marked stone alongside of the pipe. No trees within limits. Placed 54-2 and 54-4 on a steel fence post 5' east and placed 54-2 on a steel fence post 5' west of the corner. Raised a mound of stone 3 ft. base, 3 ft. high, 6 ft. west of corner.



I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David Cummins Daniel Rowland Douglas Moser

February 3, 1981



Signature of Barry B. Barbour and Oregon Land Surveyor stamp.

Office of... County Surveyor... County of... Baker... State of... I hereby certify that the within instrument was filed in this office for record on the... day of... 1981... by... (DEPUTY)

FILED... July 27, 1981... BAKER COUNTY SURVEYOR... SURVEY NO. 7-47-44