


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. R-13

History of original corner establishment:

Corner was originally established under G.L.O. contract number 707, By Williard B. Blakeslee on June 10, 1901. Surveyor General's notes state: "Set a basalt stone 32 X 17 X 14 ins., 20 ins. in the grd., for the cor. to secs. 21-22-27-28 marked with 2 notches on the S. and 3 on the E. faces, raised a mound of stone 3 ft. base 24 ins., high 10 lks. W. of the cor. (Pits Imp)."




Description of corner evidence found:

Found a 32 X 17 X 14 inch stone set in a mound of stone, marked with 2 notches on the South, 3 notches on the East and 4 notches on the underside as it currently set. Found remains of mound of stone 10 lks. West.

Description of monument and accessories established to perpetuate the original location of this corner:

At the center of the above point, set 2 1/12" X 30" galvanized pipe and brass cap marked: Set pipe 22" in the ground and mound of stone around to cap. Buried marked stone alongside of the pipe.




From which by magnetic declination of N20°E:
 A 27" pine bears N44°E, 145.0 ft. scribed T7S R47E S22 BT. A 30" pine bears 539°W, 114.1 ft. scribed T7S R47E S28 BT. A 24" pine bears N70°W, 99.0 ft. scribed T7S R47E S21 BT.
 Painted blazes red and 6" red band around. Placed 54-3s, 54-4s, and brass washers stamped PLS 1051 on the BT's. Placed 54-4 on a steel fence post 5' north and raised a mound of stone 3 ft. base, 3 ft. high, 5 ft. west of corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: David Cummins
 Daniel Rowland
 Douglas Noser

January 26, 1981



Barry B. Barbour
 OREGON
 OCT. 17, 1973
 BARRY B. BARBOUR
 1031

Office of.....County Surveyor..... County of.....Baker.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19..81
 by
 (COUNTY OFFICIAL) (DEPUTY)

FILED July 27, 1981
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-47-47