


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. G-21

History of original corner establishment:

Corner was originally established under G.L.O. contract No. 707 by Willard B. Blakeslee on June 5, 1901. Surveyors General's notes state: "falls on solid rock in place 20 x 20 x 20 ins., above gro., I cut a (+) cross at the exact cor., pt. and marked 1/4 S. on the W. face for 1/4 Sec., cor. from which a fir tree 8 ins., in diam. brs., N65°E, 75 lks., dist. marked 1/4 S12. B.T. and a fir 10 ins., in diam. brs., N68°W, 50 lks., dist., marked 1/4 S11. B.T."



Description of corner evidence found:

Found no trace of record stone. Measured S65°W, 34.5 ft. to a hole where a large rock had been, from a 28" fir with grown over blazes. From here a 24" fir bears N74°E, 52.6 ft. with grown over blazes.

Description of monument and accessories I established to perpetuate the original location of this corner:


At center of hole set 2 1/2" x 30" galvanized pipe and brass cap marked:
Set pipe 25" in the ground and mound of stone around to cap. Painted 6" red band around old BTs. Placed 54-3s and 54-4s on BTs. Placed 54-4 on a steel fence post 5' North of the corner.

T7S R47E
1/4
S11 + S12
OR PLS 1051
1981

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel Rowland
Dave Poe

October 22, 1981



Barry B. Barbour
OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office for record on the...25...day of...January....., 19...82
.....County Surveyor..... by.....Tom Healy.....
(COUNTY OFFICIAL) (DEPUTY)

FILED Jan 25, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 7-47-58