

NARRATIVE OF SURVEY

Survey of certain parcels of land in the NW $\frac{1}{4}$ NW $\frac{1}{4}$ of Section 20, T 7 S, R 48 E, W.M., at the request of George Parker and Bill Brown on April 28, 1980.


METHOD OF SURVEY

Survey control points for Survey No. 7-48-3, filed Oct. 17, 1974, were recovered to provide a common control for this survey. The corner to Sections 17, 18, 19 and 20 was found and tied to during the course of unrelated work in February, 1979. Said corner being a stone, firmly set, and marked with 5 notches on the east edge.

From the Deed records and an unrecorded map of survey work performed by Lawrence K. Monroe, RPE 1413, Idaho, the monuments shown on this map were located. The northeast corner of TRACT 1 was re-established on the west right-of-way of the Baker-Homestead Hwy at the record distance from the found southeast corner of TRACT 1. The north and south boundaries were then marked on the ground with wood stakes.

A new parcel of land was then established with 60 feet of frontage along the west right-of-way line of the Baker-Homestead Hwy and being parallel to the south boundary of TRACT 1 for the north and south boundaries.

This narrative accompanies the Map of Survey and is made a part thereof.



William L. Hanley

