



P.I. BENT REBAR, LOOSE IN GND.
(90+04.64)

LEGEND

- Found O.S.H.D. monument of record 5/8" rebar
 - Set 5/8" x 30" rebar with plastic cap mkd. "HANLEY ENGR. PLS 1206"
 - () Record data O.S.H.D. Drawing 8B-11-17 and/or Deed No. 91 06 085
- SCALE 1" = 100'

NARRATIVE

The purpose of this survey for George and Judy Parker is to mark on the ground a property ownership line as described in Deeds 82 08 061, 91 06 085 and Partition Plat P-1990-004. O.S.H.D. monumentation was recovered as shown and held as the basis of bearing for this survey. The O.S.H.D. record distance between P.I. monuments differs from this survey by 2.86 feet as shown hereon. The Southerly monument having been found undisturbed and in good shape was accepted as occupying it's correct position. The Southwest corner of Section 17 was not remeasured to as part of this survey, shown hereon from record tie in Deed 91 06 085. Deed references: Bk. 171, Page 1325, 82 18 061 and 91 06 085. Survey references: Survey No. 7-48-5, 7-48-9, Partition Plat No. P-1990-004 and O.S.H.D. Drawing 8B-11-7.

MAP OF SURVEY
IN THE
SW 1/4 SEC. 17, T. 7 S., R. 48 E.
FOR: GEORGE AND JUDY PARKER
SURVEYED OCT. 14, 1992

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley

OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

HANLEY ENGINEERING
P.O. BOX 701
2043 MAIN STREET
BAKER CITY, OREGON

FILED March 1, 1993
BAKER COUNTY SURVEYOR
SURVEY NO. 7-48-11