


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-25 T 8 S R 36 E

History of original corner establishment:

Corner established by Lincoln E. Wilkes under instructions dated Sept. 24, 1923 and included in Group No. 107.



Surveyor General records state:

...set an iron post, 3 ft. long, 1 in. dia., 27 ins. in the ground, for  $\frac{1}{4}$  sec. cor. of sec. 24 only, with brass cap marked as shown in corner diagram from which:

- A spruce, 9 ins. dia., bears S.  $23\frac{1}{2}^{\circ}$  W., 22 lks. dist., marked  $\frac{1}{4}$  S 24 BT,
- A spruce, 6 ins. dia., bears N.  $79^{\circ}$  W., 31 lks. dist., marked  $\frac{1}{4}$  S 24 BT.

Description of corner evidence found:

- An brass cap on an iron pipe marked as shown in corner diagram.
- A 13" diam. spruce snag bears S  $23\frac{1}{2}^{\circ}$  W., 22 lks. dist. with healed blaze.
- A Spruce 18" diam. bears N  $79^{\circ}$  W., 31 lks. dist. with healed blaze.

Description of monument and accessories | established to perpetuate the original location of this corner:

Improved surrounding rock mound around corner monument and set a 6 foot steel fence post alongside with a sign 54-9 attached.

New bearing tree:

A spruce 13 inches diam bears S  $56^{\circ}$  W., 24.5 ft. dist. marked  $\frac{1}{4}$  S 24 BT and has a brass washer marked PLS 1639 nailed flush with BT blaze.

To each bearing tree attached a sign 54-3 above BT blaze and below a 6 inch band of red paint and a sign 54-9 attached to opposite side of tree from BT blaze.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards under my supervision on Oct. 4, 1984, and witnessed by Jim DeMastus and Daryl Schuchardt.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

Office of County Surveyor County of Baker  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 11 day of June, 1985  
 \_\_\_\_\_ by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)

FILED 6-11-85  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 8-36-2