


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-25

History of original corner establishment:

Corner established by Lincoln E. Wilkes under instructions dated Sept., 24, 1923, and included in Group No. 107.



Surveyor General records state:

Set an iron post 3 ft long, 1 in dia, 27 ins in the ground, for 1/4 sec cor of sec 36 only, with brass cap marked

1/4S36

1924

from which:

A pine 40 ins dia bears S 53° W, 8 lks dist, marked 1/4 S 36 BT


A pine 40 ins dia bears N 31 1/2° W, 66 lks dist marked 1/4 S 36 BT

Description of corner evidence found:

The southwest bearing tree is a 45 inch dia pine with healed blaze.

The northwest bearing tree is a 40 inch dia pine with scribed visible on open blaze.

Found brass cap monument marked thus:



Description of monument and accessories I established to perpetuate the original location of this corner:

Improved surrounding rock mound around corner monument and set a 6 foot steel fence post alongside with a sign 54-9 attached.

Each original bearing tree has a sign 54-3 attached above BT blaze and has a sign 54-9 attached on the opposite side of tree and has a 6 inch band of red paint around.

I hereby certify that the above described corner monument was properly maintained to U.S.F.S. standards under my supervision on Oct. 2, 1984, and witnessed by Jim DeMastus and Daryl Schuchardt.

REGISTERED PROFESSIONAL LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Surveyor Baker County of Baker
Office of Oregon, I hereby certify that the within instrument was filed in this office
State of Oregon, for record on the 11 day of June, 1985
by (COUNTY OFFICIAL) (DEPUTY)