

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner originally established by C.M.Foster under Mineral Survey No.129 (Later renumbered MS 77) and dated July 16, 1885.

Original notes state:

A post marked S.A.H. No. 4 - 129.


Corner later used by Arthur Philbrick under Mineral Survey No.481 and dated July 11,1902.

Original notes state:

Identical with Cor.No.4, Mammoth Lode,M.S.129.

A granite stone 26x10x8 ins.set 16 ins. in the ground, with mound of stone along side, chiseled MA-129-B.B.4-481, whence A black pine,4 ins.diam.,bears N.9°55'E 11.67 ft.

A black pine,5 ins.diam.,bears S.89°26'E. 21.23 ft., each blazed and scribed B.T.M.4-129-B.B.-4-481.



Cor.4 Mammoth MS 77  
Cor.4 Bell Baker MS 481

**Description of corner evidence found:**

Found a 28x10x8" granite stone with full marking per Bell Baker survey with "X" on top, from which:

A 12" down lodgepole pine brs. N10°E, 12.0' to stump with healed blaze. (Original BT)

A 13" lodgepole stump brs. S89½°E, 21.6' with bottom of catface and visible scribes and nail. (Original BT)

A 10" standing dead lodgepole pine brs. N83½°E, 17.1' with visible scribes on partially healed blaze.(Not of record).

**Description of monument and accessories | established to perpetuate the original location of this corner:**

At position of original stone...

Set 2½" x 30" aluminum pipe with 2½" aluminum cap 24" in ground and surrounded with mound of earth & stone. Placed corner stone in new mound on NE side of new monument, cap marked as shown in corner diagram.

**New bearing trees established:**

A 13" western larch brs S47½°W, 51.5' scribed 4-M-77/4-BB-481 BT.

A 11" lodgepole pine brs S43½°E, 31.5' scribed 4-M-77/4-BB-481 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze.Attached sign 54-3 & 54-4 to each BT & painted face of blaze & 6" red band around each BT.Set steel fence post on National Forest Boundary SW of corner with sign 54-2 & 54-9 attached.

Compass declination 18° East.

I hereby certify that the above corner was properly remonumented by me to U.S.F.S. standards on September 10, 1992.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of...County Surveyor..... County of...Baker.....

State of...Oregon....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)