

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner originally established by John Hagel under Mineral Survey No.428 and surveyed under instructions dated July 10,1901.

Original notes state:

Set a pine post 4 ins.square, 4½ ft.long,18 ins. in the ground, with a mound of rocks around it, scribed Lux.Q.Cl.,N.Cen.-428.

A spruce tree 8 ins.diam.,blazed and scribed Lux.N.Cen.-428-B.T. bears N.67°05'E, 39.7 ft.



North Center Luxemburg

Description of corner evidence found:

Found rotted remains of post at ground level in mound of stone, from which...

A 14" spruce brs N68°E, 39.2' with healed blaze.(Original BT)

Description of monument and accessories I established to perpetuate the original location of this corner:

At position of found post remains...

Set 2½" x 30" aluminum pipe with 2½" aluminum cap 26" in ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

New bearing trees established:

A 10" lodgepole pine brs S70½°E, 27.3' scribed NC-L-428 BT.

A 8" lodgepole pine brs S03½°E, 29.6' scribed NC-L-428 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze.Attached sign 54-3 & 54-9 to each BT & painted face of blaze & 6" red band around each BT. Set steel fence post on National Forest Boundary SE of corner with sign 54-2 & 54-9 attached.

Compass declination 18° East.

I hereby certify that the above corner was properly remonumented by me to U.S.F.S. standards on September 11, 1992.

REGISTERED PROFESSIONAL LAND SURVEYOR

*William R. Wells*

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of.....County Surveyor..... County of..... Baker.....

State of..... Oregon....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

FILED 3-24-93

BAKER COUNTY SURVEYOR

SURVEY NO. 8-36-79