

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Arthur Philbrick under Mineral Survey No.481 and dated July 11, 1902.

Original notes state:


A black pine post, 4 ft. long, 4 ins. square, set 12 ins. in the ground, with mound of earth, scribed B.B.3-R.F.3-481, whence

A red fir 48 ins. diam. bears S53°30'W, 17.98 ft.

A red fir 20 ins. diam. bears N22°E, 15 ft., each blazed and scribed B.T.B.B.3-R.F.3-481.

Corner amended by Arthur Browne under Mineral Survey No.481 and dated May 14, 1904. Original notes state:

Scribing on post changed to read R.F.4-481, scribing on two bearing trees, as given in notes of original survey, also changed to read B.T.R.F.4-481.



Cor.3 BELL BAKER
Cor.4 RED FOX AMD

Description of corner evidence found:

No trace of original pine post.

A 29" dia. douglas fir stump brs N22°E, 16.2' to centerline (15.0' to face) with marks "481" visible.

Description of monument and accessories | established to perpetuate the original location of this corner:

Reset corner from record bearing and distance from found bearing tree face...

Set 2½" x 30" aluminum pipe with 2½" aluminum cap 28" in ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

New bearing trees established:

A 28" dia. western larch brs N9 3/4°W, 94.1' scribed 3-BB-481/4-RF-AMD-481 BT.

A 12½" dia. lodgepole pine brs N51°W, 66.9' scribed 3-BB-481/4-RF-AMD-481 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 to each BT & painted face of blaze & 6" red band around each BT. Set steel fence post on National Forest Boundary NE of corner with sign 54-2 & 54-9 attached.

Compass declination 18° East.

I hereby certify that the above corner was properly re-established by me to U.S.F.S. standards on September 10, 1992.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of... County Surveyor..... County of... Baker.....
State of... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)