

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Charles M. Foster under Mineral Survey No. 505, surveyed under instructions dated April 5, 1904.

Original notes state:

A pine post 4 ft. long, 4 ins. square, set 18 ins. in the ground, surrounded with a mound of earth, scribed C-5-505.

T 8 S R 36 E
MS 505
5 C

Casaubon Cor. 5

Corner was remonumented by: William R. Wells during Corner Record 8-36-88, dated 3-24-93.

Found rotted remains of post at ground level, after determining search area by survey.

At position of found post remains...

Set a 2 1/2" x 30" aluminum pipe with a 2 1/2" aluminum cap 28" in ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram. Placed post remains on the new mound.

New bearing trees established:

- A 9" western larch brs S03 1/4°W, 61.9' scribed 5-C-505 BT.
- A 8" western larch brs S54 1/2°W, 52.1' scribed 5-C-505 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached 54-3 & 54-9 to each BT & painted face of blaze & 6" red band around each BT. Set a steel fence post on Nation Forest Boundary NE of corner with sign 54-2 & 54-9 attached.

Compass declination 18° East

I hereby certify that the above corner was properly remonumented by me to U.S.F.S. standards on September 16, 1992.

Description of corner evidence found:


A 2 1/2 inch aluminum pipe with a 2 1/2 inch aluminum cap, marked as shown. Firmly set flush with ground, with a rock collar.

From which:

A 9 inch western larch (by Wells) high-cut stump with visible scribing "5-C-505-BT" bears S3 1/4°W, 61.9 feet.

An 8 inch western larch snag (by Wells) dead and down, bears S54 1/2°W, 52.1 feet to stump hole.

A steel T-post bears N58°E, 3.0 feet; with sign: Property Boundary



Description of monument and accessories I established to perpetuate original location of this corner:

New Bearing Trees:

A 9 inch lodgepole pine scribed "C5 505 BT" bears N47°E, 14.5 feet; measured to a 3/4 inch brass washer mkd: "LS 91201", at the right side of tree center.

A 12 inch lodgepole pine scribed "C5 505 BT" bears N 72 1/2°W, 33.8 feet; measured to a 3/4 inch brass washer mkd: "LS 91201", at the right side of tree center.

A sign was added to existing T-post: Land Survey Monument

NAD 83 Geodetic Position

Lat. 44°49'28.5" N
Long. 118°15'24.7" W

Established by: Garmin ETREX 32x

I hereby certify that the corner is monumented and accessories taken as described using a steel tape and a Warren Knight staff compass, set with a declination of 14° East.

Witnesses: David Quittschreiber, Justin Seal, Shar Hutchison

August 9, 2023

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Krist Powell

OREGON
MAY 9, 2017
KRISTINA POWELL
91201

EXPIRES 12-31-24

FILED January 3, 2024

BAKER COUNTY SURVEYOR
SURVEY NO. 8-36-101