

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Original corner established by John Hagel under Mineral Survey No. 427 and surveyed under instructions dated July 8, 1901.

Original notes state:

Identical with No. 1 of Luxemburg Quartz Claim, Survey 428. Set a white pine post 4 ins. square, 4 1/2 ft. long, 18 ins. in the ground with a mound of earth around it, scribed Alta Q. Cl. C. 1-427. The southwest loc. Cor. bears S38°49'E, 95.0 ft.

A black pine tree 6 ins. diam. bears N45°45'W, 74.5 ft.
A black pine tree 6 ins. diam. bears N32°15'W, 73.0 ft., both blazed and scribed Q.Cl. C.1-427-BT.

Corner established by: John Hagel under Mineral Survey No. 428 and dated July 10, 1901.

Record states:

Identical with Corner No. 1 of the "Alta" Quartz Claim. A white fir post 4 ins. square, 3 ft. above the ground, with a mound of earth around it, scribed Alta C.1-427. Scribed it Lux. C.1-428.

A black pine tree 6 ins. diam. bears S.72°30'E, 39.1 ft.
A black pine tree 4 ins. diam. bears N.60°W, 31.0 ft. both blazed and scribed Lux. C.1-428 BT.

Corner was remonumented by: William R. Wells per Corner Record 8-36-68, recorded 3-24-93.

Found a post hole with rotted post remains at and below ground surface, from which...

A 10" down lodgepole pine brs N32 1/4°W, 73' +/- to root hole with scribes visible on opened blaze. (Original BT).

At position of found post remains, from which...

Set 2 1/2" x 30" aluminum pipe with 2 1/2" aluminum cap 28" in ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

New bearing trees established:

A 12" western larch brs S30 1/2°E, 82.2' scribed 1-A-427 / 1-L-428 BT.
A 11" lodgepole pine brs N71 1/2°W, 36.5' scribed 1-A-427/1-L-428 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze & 6" red band around each BT. Set steel fence post on National Forest Boundary NE of corner with a sign 54-2 & 54-9 attached.

Compass declination 18° East.

I hereby certify that the above corner was properly remonumented by me to U.S.F.S. standards on September 10, 1992.

T 8 S R 36 E
MS 427 / MS 428
1 A / 1 L

Luxemburg Cor. 1

Alta Cor 1

Continued on page 2 of 2

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Kristina Powell

OREGON
MAY 9, 2017
KRISTINA POWELL
91201

EXPIRES 12-31-24

FILED January 3, 2024
BAKER COUNTY SURVEYOR
SURVEY NO. 8-36-98

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by John Hagel under Mineral Survey No. 427 and surveyed under instructions dated July 8, 1901.

Original notes state:

Identical with cor. 2 of "Luxemburg" Quartz Claim Sur. 428.

Set a black pine post 5 ins. square, 4 1/2 ft. long, 18 ins. in the ground with a mound of earth around it, scribed Alta Q. Cl. C.2-427.

A spruce tree 5 ins. diam. bears S34°15'E, 9.8 ft.
A black pine tree 12 ins. diam. bears S78°E, 11.8 ft.
both blazed and scribed Alta Q.Cl. C.2-427 BT.

Corner established by: John Hagel under Mineral Survey No. 428 and dated July 10, 1901.

Record states:

Identical with the Corner No. 2 of the "Alta" Quartz Claim, survey 427.

A black pine post 5 ins. square, 3 ft. above the ground, with a mound of earth around it, scribed Alta Q.Cl. C.2-427. Scribed it Lux.Q.Cl. C.2-428.

Corner remonumented by: William R. Wells, per Corner Record 8-36-69, filed 3-24-93.

Found rotted remains of post below ground level, from which...

A 38" spruce brs S34 1/4°E, 9.8' with healed blaze. (Original BT)
A 18" lodgepole pine brs S78°E, 11.7' with scribes visible on a previously opened blaze. (Original BT)

At position of found post remains...

Set 2 1/2" x 30" aluminum pipe with a 2 1/2" aluminum cap 28" in ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

New bearing trees established:

A 22" western larch brs N58°W, 49.9' scribed 2-A-427/2-L-428 BT.
A 17" western larch brs S63 1/2°W, 45.0' scribed 2-A-427/2-L-428 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 to each BT & painted face of blaze & 6" red band around each BT. Set steel fence post on National Forest Boundary SW of corner with sign 54-2 & 54-9 attached.

Compass declination 18° East.

I hereby certify that the above corner was properly remonumented by me to U.S.F.S. standards on September 15, 1992.

Continued on page 2 of 2

T 8 S R 36 E
MS 427 / MS 428
2 A / 2 L

Luxemburg Cor. 2

Alta Cor. 2

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Kristina Powell

OREGON
MAY 9, 2017
KRISTINA POWELL
91201

EXPIRES 12-31-24

FILED January 3, 2024
BAKER COUNTY SURVEYOR
SURVEY NO. 8-36-99