


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX MS 800

History of original corner establishment:



A. Ira L. Hoffman, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 800 surveyed the Richard Woods claim known as Morning Star Lode from October 11, 1917 to September 19, 1918 and approved by the U.S. Surveyor General's Office 19 November, 1918. Otis O. Gould, U.S. Deputy Surveyor did a dependent resurvey under special instructions dated 27 Nov. 1935, and approved 17 August, 1939.

SURVEYOR GENERAL'S RECORD STATES: (Otis O. Gould)

Set an iron post, 3 ft. long, 1 in. diam., 27 in. in the ground, for Cor. No. 3, Morning Star lode, with brass cap marked: from which

A tamarack, 8 ins. diam., bears N39-30W, 7 lks. dist. marks grown over. (Old B.T.)	3 MS 800
A tamarack, 10 ins. diam., bears S72-30W, 13 lks. dist., marks grown over. (Old B.T.)	1937

B. MONUMENT FOUND:

I found a 2.5" dia. brass cap on a 1.0" dia. iron pipe 7.5" exposed in a loose mound of stone. The cap was marked:

U S GENERAL LAND OFFICE SURVEY
PENALTY \$250 FOR REMOVAL

3 MS 800 1937

ACCESSORIES FOUND:

8" dia. Western Larch bears N39-30W, 4.7 ft., with healed blaze. dead and down Western Larch with visible blaze and scribing.

Description of monument and accessories established to perpetuate the original location of this corner:

CORNER WORK DONE ON 6/8/90

C. Restacked the stone mound and added stones to the top of the monument.

NEW ACCESSORIES ESTABLISHED

A Western Larch, 8" dia., bears N34W, 4.8 ft., scribed COR3MS800 BT
A Douglas fir, 12" dia., bears N35E, 5.7 ft., scribed COR3MS800 BT

Painted the blaze red on each BT
Painted a 6" wide red band around each BT
Placed brass washer marked "PLS 2060" at base of each BT blaze
Placed metal sign with bearing and distance information on each BT (54-3)
Placed metal ATTENTION sign on each BT (54-4)
Placed 6 ft. steel fence post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4) attached
I measured to the centerline of each bearing tree using tape and hand compass with declination set at 20 degrees east.

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>Edwin A. Stryker</i>
OREGON JULY 15, 1983 EDWIN A. STRYKER 2060

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED 11-16-1990
BAKER COUNTY SURVEYOR
SURVEY NO. 8-36-56