


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX MS 485

History of original corner establishment:

A. Arthur Philbrick, U.S. Deputy Mineral Surveyor, under Mineral Survey No. 485 surveyed the Peter D. Estes and Joseph D. Young claim known as the Gold Hill Lode Mining Claim 27 July, to 28 July, 1902 and approved by the U.S. Surveyor General's Office.



SURVEYOR GENERAL'S RECORD STATES:

Identical with Cor. No. 2, Red Fox Lode, MS 481. A red fir post, 4 ft. long, 4 ins. square, set 12 ins. in the ground, with mound of earth, scribed RF 2 481 GH 4 485, whence Location Cor. bears N18-50W, 19.52 ft. A red fir, 6 ins. diam., bears N25-14W, 23.80 ft., a red fir, 6 ins. diam., bears S68-36W, 34.86 ft., each blazed and scribed BT RF 2 481 GH 4 485

Description of corner evidence found:

B. MONUMENT FOUND:

I found a 5"x5"x11" remains of wood post 20" in the ground with pointed end.


ACCESSORIES FOUND:

20" dia. Grand Fir with healed blaze bears S71W, 35.4 ft. (did not open) Rotted remains of true fir stump bears N20W, 23.3 ft., with down bole and visible scribe of "2 481 GH 4 485"

Description of monument and accessories I established to perpetuate the original location of this corner:

CORNER WORK DONE ON 6/19/90

C. At the position of the pointed post remnant, set a 2.5" dia. by 30" long aluminum pipe with a 2.5" dia. aluminum cap. The pipe is set 26" in the ground with earth to the top. No stones available. The cap is marked



NEW ACCESSORIES ESTABLISHED

STRYKER PLS 2060

18" dia. Grand Fir bears N54W, 6.5 ft.; scribed 2 RF 481 4 GH 485 BT

Painted the blaze red on each BT
Painted a 6" wide red band around each BT
Placed brass washer marked "PLS 2060" at base of each BT blaze
Placed metal sign with bearing and distance information on each BT (54-3)
Placed metal ATTENTION sign on each BT (54-4)
Placed 6 ft. metal guard post at corner with metal PROPERTY BOUNDARY sign and metal ATTENTION sign (54-2 and 54-4)
I measured to the centerline of each bearing tree using tape and hand compass with declination set at 20 degrees east.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED PROFESSIONAL LAND SURVEYOR
Edwin A. Stryker
OREGON JULY 15, 1983
EDWIN A. STRYKER
2060