

# RECORD OF LAND CORNER MONUMENTATION

SOUTHEAST CORNER SECTION 29, T. 8 S., R. 37 E., W.M.

**ORIGINALLY ESTABLISHED BY:** Lincoln E. Wilkes, U.S. Cadastral Engineer

**GROUP NUMBER:** 107

**APPROVAL DATE:** May 26, 1927

**SUBSEQUENT SURVEYS:** Corner maintenance activities performed June 11, 1985 by William L. Hanley, PLS #1639, as evidenced by the Certified Record of Land Corner Monumentation filed February 5, 1986, as Baker County Survey No. 8-37-80

19	20			20	21
30	29			29	28
30	29			29	28
31	32			32	33

**ORIGINAL DESCRIPTION:** Set an iron post, 3 ft. long, 2 ins dia., 27 ins. in the ground, for cor of secs. 28, 29, 32, and 33, with brass cap marked (diagram shown) from which  
 A white fir, 8 ins. dia., bears N. 18° E., 83 lks. dist., marked T 8 S R 37 E S 28 BT.  
 A Douglas-fir, 5 ins. dia., bears S. 67° E., 112 lks. dist., marked T 8 S R 37 E S 33 BT.  
 A quaking asp, 7 ins. dia., bears S. 48° W., 74 lks. dist., marked T 8 S R 37 E S 32 BT.  
 A yellow pine, 42 ins. dia., bears N. 16 1/2° W., 46 lks. dist., marked T 8 S R 37 E S 29 BT.


**HANLEY'S DESCRIPTION:** A brass cap of record dimensions and markings as shown in corner diagram.  
 A ponderosa pine 45 ins dia bears N 16 1/2°W, 46 lks with scribes visible.  
 A douglas fir 24 ins dia bears S67°E, 112 lks with healed blaze.  
 A white fir 17 ins dia bears N18°E, 83 lks with healed blaze.  
 No sign of the aspen.  
 Improved surrounding rock mound around recovered corner monument and set a 6 foot steel fence post alongside with a sign 54-9 attached.  
 New bearing tree established:  
 A douglas fir 11 ins dia bears S21°W, 43.6 ft marked T8SR37ES32BT.

**EVIDENCE FOUND:** Found 2" iron pipe with 2 1/2" brass cap, marked as shown below, projecting 16" above ground in a 2.5 ft. diameter mound of stone, with a steel fence post with attached USFS 54-9 sign set Northwest, 3.5 ft. from monument.

- From which:
- ▶ A white fir, 23" dbh, bears N.18°E., 54.8 ft. (GLO BT).
  - ▶ A Douglas-fir, 30" dbh , bears S.67°E., 73.9 ft., with healed double blazes (GLO BT).
  - ▶ A Douglas-fir, 23" dbh, bears S.21°W., 43.6 ft., with healed double blazes (Hanley BT).
  - ▶ A ponderosa pine, 44" dbh, N.16 1/2 °W., 30.4 ft., with visible scribing in a partially healed blaze (GLO BT).

**DESCRIPTION OF MONUMENTS AND ACCESSORIES SET AND METHODS USED:**  
 I accept the position of the found monument for the corner.

CORNER MONUMENT MARKED:



Painted a 6 inch red band around each bearing tree, and also painted the blazes red. See associated Map of Survey dated October 17, 2023 for more survey-related information.

**RESTORATION BY, STAMP AND DATE:**

Work Performed July 7, 2023  
 Survey completed October 17, 2023

Toribio J. Quinones, LSIT  
 Spencer B. Jones, Survey Tech

USDA FOREST SERVICE  
 NORTHEAST OREGON LAND ZONE  
 1550 Dewey Avenue, Suite A  
 Baker City, OR 97814  
 (541) 523-1283

FILED December 30, 2023  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 8-37-161

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON  
 NOVEMBER 30, 2007  
 JASON L. HATFIELD  
 #69454

EXPIRES: 6/30/2025