


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

**HISTORY OF ORIGINAL CORNER ESTABLISHED:**

Corner established in 1972 by Leland Meyers in Plat of Canyon Park. Not described.

Corner shown in Survey Number 08-38-0012 as 5/8" x 30" Rebar.

T 8 S R 38 E R-18



**DESCRIPTION OF CORNER EVIDENCE FOUND:**

Found 5/8" iron pin rebar, 4 inches above ground.

**DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO MONUMENT THE ORIGINAL LOCATION OF THIS CORNER:**

From the iron pin:

**NEW BEARING OBJECTS:**

A 14" White Fir bears South 58° East, a distance of 6.00 feet, marked W1/16 S26 BT.

A 10" White Fir bears North 3° West, a distance of 8.15 feet, marked W1/16 S23 BT.

I hereby certify that the corner was perpetuated on November 5, 2020.

Witness: Kyle A. Tucker



Renewal Date: June 30, 2021

I used a steel tape and magnetic compass in the establishment of the new accessories. I used 14° East declination, the distances are to a 60d spike driven into the right side of the root crown of the bearing trees. A brass washer marked OPLS 83571 is attached to the BT blaze of the new bearing trees.

FILED November 18, 2020  
BAKER COUNTY SURVEYOR  
SURVEY NO. 8-38-150