

NARRATIVE TO ACCOMPANY SURVEY
OF SECTION 29, T. 8 S., R. 42 E., W.M.

This survey for Farm Credit Services was made for the purpose of marking on the ground the corners of the NE $\frac{1}{4}$ SE $\frac{1}{4}$ of Section 29, T. 8 S., R. 42 E., W.M.

The township was originally surveyed under GLO Contract No. 235, dated July 6, 1875 by John H. Stone, and performed between August 7 and 18, 1875.

The following concerns the corner monumentation described in notes of the original survey and the results of search for existing monumentation for Section 29.

The original Southwest corner monumentation consisted of a wood post. The Oregon State Highway Department Drawing No 6B-6-15 of the relocated Baker-Ruckles Creek Section, dated December, 1942 states a mound of stone was found at this location, which was recovered during this current survey.

The original corner monument for the South quarter corner was a wood post. OSHD found a stone which was also recovered at this time. The stone was clearly marked with "1/4" scribed on the stone face and was firmly set in the ground. The stone was replaced with a 2-inch brass cap on 1-inch iron pipe monument with the appropriate markings for this corner.

The original Southeast section corner consisted of a 16 x 14 x 12 inch stone, indicated on the OSHD map as found, and was recovered during this survey. The stone shows signs of some additional marks believed as result of being struck by a farm disc.

The original East quarter corner was a 18 x 16 x 12 inch stone. The OSHD map describes this stone being 2676.7 feet from the Southeast section corner. This survey found a mound of stones 2675.8 feet distant from the said quarter corner, and accepted the mound as being the proper location for the corner.

The West quarter corner consisted of a wood post, and falls in a cultivated area. No trace of any monumentation was found.

The original North quarter corner consisted of a wood post and mound. A Baker County road was built along the North-South mid-section line. Reestablishment of this location was made along the road centerline at its intersection with the projected fencing line along the North line of this section.

The Northwest section corner was not found. The North section line is fenced in this vicinity, and is accepted as being the true section line. The lost West quarter corner is relocated midway between the fence line and the Southwest section corner for the purpose of computing the bearing from the East quarter corner for the center of section computation.

The corners of the NE $\frac{1}{4}$ SE $\frac{1}{4}$ were established using the above criteria.

FILED Nov 4, 1988

BAKER COUNTY SURVEYOR

SURVEY NO. 8-42-2