

Narrative Section 29 continued

The intersection of the county road right of way with the West line of the said NE $\frac{1}{4}$ SE $\frac{1}{4}$  and the SE $\frac{1}{4}$ NE $\frac{1}{4}$  was monumented for Lee Bates at the request of attorney Steve Corey. This additional work required location of the Northeast section corner, considered lost, and was reestablished by proportionment of plat distance between the found North quarter corner of Section 28 and the re-established North quarter corner of Section 29 along the existing East-West fence lines.

The several stone monuments found by the Oregon State Highway Department described in the original field notes as consisting of wood posts are believed to be replacements set by former County Surveyor Ira Hoffman, although I can find no documentation in his early field records. Stones marked "1/16" were found near the Southwest and Southeast corners of the NE $\frac{1}{4}$ SE $\frac{1}{4}$ , and are probably the result of early subdivisional survey of this section. These found stones are depicted on the accompanying map of survey.

*James D. Hanley*  
James D. Hanley  
PLS 1206

FILED Nov 4, 1988  
BAKER COUNTY SURVEYOR  
SURVEY NO. 8-42-2