

NARRATIVE TO ACCOMPANY SURVEY NO. 8-42-3

The purpose of this survey for Farm Credit Services is to show the relationship of the existing fencing and deeded property lines in Sections 17, 19, 20, 29, 30, 32, T. 8 S., R. 42 E., W.M., Baker County, Oregon.

J. Stone surveyed the West range line, the South township line and the interior lines of T. 8 S., R. 42 E., W.M., under GLO contract no. 235, approved 2/29/1876.

W. Barr resurveyed the South township line under GLO contract no. 388, approved 12/31/1881.

31 | 32
6 | 5
The section corner common to Sections 5, 6, 31 and 32: J. Stone's GLO record states "set a stone 22 x 7 x 6...". W. Barr's GLO record states "Rock 22 x 7 x 6 agreeing with description...". This survey found stone 20 x 10 x 8 lying flat on the ground mkd. with 6 notches on two edges.. Set a 5/8 inch x 30 inch long rebar in stone's position with yellow plastic cap mkd. "HANLEY ENGRG PLS 1206". Placed original stone alongside.

1/4 32
5
The South quarter corner of Section 32: J. Stone's GLO record states "Set a stone 16 x 7 x 6"... W. Barr's GLO records state "Rock 16 x 7 x 6 agreeing with description...". This survey found stone 16 x 10 x 7 marked with 1/4 on face, lying flat on the ground. Set a 5/8 inch rebar in stone's position with plastic cap mkd. "HANLEY ENGRG PLS 1206", and placed the stone on top of rebar.

1/4 31
36 | 31
The West quarter corner of Section 31: GLO records state "Set a stone 16 x 9 x 7...". This survey found stone 14 x 10 x 4 well set in the ground with faint 1/4 mkd. on the East face. Set a 5/8 inch x 30 inch rebar in stone's position with yellow plastic cap mkd. "HANLEY ENGRG PLS 1206 and placed the stone on top of rebar.

1/4 31 | 32
31 | 32
The quarter corner common to Sections 31 and 32: GLO records state "Set post.... raised mound and trench..." No evidence of original post or trench was found. Point was reestablished by single proportion method between North and South section corners, and not remonumented this survey.

1/4 32 | 33
32 | 33
The quarter corner common to Sections 32 and 33: GLO record states "Set stone 14 x 13 x 10 for 1/4 sec. cor.". This survey found deeply set stone mkd. with 1/4 on East face and X on top of stone. Did not disturb stone. Did not remonument.

25 | 30
36 | 31
The section corner common to Sections 25, 30, 31 and 36: GLO records state "Set a post with mound and trench...". No evidence of post or trench was found. Point was reestablished by single proportionate method along the range line between found corners North and South. Did not remonument this survey.

30
31
The quarter corner common to Sections 30 and 31: GLO records state "Set post...raised mound and trench...". Found 42 inch diam. stone mound. Set a 5/8 inch x 30 inch rebar with plastic cap mkd. "HANLEY ENGRG PLS 1206" in center of stone mound.

30 | 29
31 | 32
The section corner common to Sections 29, 30, 31 and 32: GLO records state "Set post...raised mound and trench...". This survey found 36 inch diam. stone and earthen mound. Set a bridge spike in center of mound. Did not remonument.

NARRATIVE continued Page 2

1/4 29
32
The quarter corner common to Sections 29 and 32: GLO records state "Set post...raised mound and trench...". This survey found a basalt stone 18 x 14 x 12 deeply set in the ground, marked 1/4 on North face and in North-South running fence line. Set a 2 1/2-inch diam. brass cap on 1 1/4-inch x 30 inch iron pipe 24 inches in the ground and constructed a 36 inch diam. stone mound around the monument. Buried the found stone 1 foot North. Additional information is shown on Baker County Survey No.8-42-4.

29 | 28
32 | 33
The section corner common to Sections 28, 29, 32 and 33: GLO records state "Set stone 16 x 14 x 12 for cor. to secs. 28, 29, 32 and 33...". This survey found stone 18 x 12 x 4 mkd. with faint notches on one edge of the stone. Stone was lying flat on the ground. Set a 5/8 inch x 30 inch rebar in stone's position with yellow plastic cap mkd. "HANLEY ENGRG PLS 1206". Placed stone on top of rebar.

1/4 25 | 30
The West quarter corner of Section 30: GLO records state "Set a willow post with mound and trench...". No original evidence found. Point was located by the intersection of an established East-West running fence line and the range line as defined by the section corner 1 1/2 miles North and the quarter corner 1 mile South. Point was not remonumented this survey.

1/4 30 | 29
The quarter corner common to Sections 29 and 30: GLO records state "Set post.... raised mound and trench...". No evidence found of original monumentation. Point was reestablished by single proportionate method between section corners South and North. Set a 5/8 inch x 30 inch rebar with yellow plastic cap mkd. "HANLEY ENGRG PLS 1206".

1/4 29 | 28
The quarter corner common to Sections 28 and 29: GLO records state "Set stone 18 x 16 x 12 for 1/4 sec. cor.". Found vesicular basalt stone 12 x 12 x 12 in center of 5 stone mound on undisturbed slope. Stone is faintly marked on one face. Point not remonumented this survey.

24 | 19
25 | 30
The section corner common to Sections 19, 24, 25 and 30: GLO records state "Set a willow post with mound and trench...". No original evidence found. Point was reestablished by the intersection of an existing East-West running fence line and the range line defined by the section corner 1 mile North and the quarter corner 1 1/2 mile South. Point was not remonumented this survey.

1/4 19
30
The quarter corner common to Sections 19 and 30: GLO record states "Set stone 14 x 12 x 10 for 1/4 sec. cor." Found a 4-way fence intersection. Set 5/8 inch x 30 inch rebar with yellow plastic cap mkd. "HANLEY ENGRG PLS 1206".

19 | 20
30 | 29
The section corner common to Sections 19, 20, 29 and 30. GLO records state "Set stone 18 x 16 x 11 for cor. to secs. 19, 20, 29 and 30. No original evidence was found. Point reestablished by proportionate method between quarter corners East and West in the existing East-West running fence line. Point was not remonumented this survey.

1/4 20
29
The quarter corner common to Sections 20 and 29: GLO records state "Set post....raised mound and trench...". No original evidence found. Point reestablished by the intersection of the centerline of Baker County Road No. 859 and the section line as defined by section corners West and East. Point was not monumented this survey.