

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-7

History of original corner establishment:

This survey of the subdivisional lines of T. 8 S. R. 42 E. W.M., was performed by Deputy Surveyor John H. Stone under contract # 235, dated July 6, 1875.

GLO notes state:

Set post 4 ft. long, 4 ins. in dia., 1 ft. in ground, and raised mound and bench as per instructions for the 1/4 sec. cor.

DIAGRAM

T 8 S R 42 E

S 29

1/4

S 32

CS

1988

Description of corner evidence found:

Found a stone 18 x 14 x 12 ins. with a prominent 1/4 on the north face. The stone was sturdily set in a N-S running fence.

Description of monument and accessories established to perpetuate the original location of this corner:

At the location of the found corner stone: Set a 2 1/2 in. brass cap on a 1 in. dia. x 30 in. long iron pipe with a 36 in. dia. stone mound constructed around it. Set a steel fence post 3 ft. north with a USFS 54-9 sign attached. Buried the corner stone 1 ft. north of the new monument. The brass cap is marked as shown in the corner diagram.

Remarks:

I believe Ira Hoffman (Baker County Surveyor in the early 1990's) set this corner at the true GLO corner point replacing the wood post that is of GLO record. Two 1/16 corner stones were found, the SE 1/16 of section 29 and the S 1/16 corner between sections 28 and 29. It is believed that these corners were set by Hoffman giving credence to his perpetuation of this 1/4 corner.

I certify that the above corner was perpetuated properly by standard survey methods as witnessed by Tom Fisk and Larry McBroom on October 6, 1988.

REGISTERED PROFESSIONAL LAND SURVEYOR

James D. Hanley OREGON SEPTEMBER 23, 1977 JAMES D. HANLEY 1206

Office of County Surveyor County of Baker State of OR I hereby certify that the within instrument was filed in this office for record on the day of 19 by (COUNTY OFFICIAL) (DEPUTY)

FILED Nov. 2 1989

BAKER COUNTY SURVEYOR

SURVEY NO. 8-42-4