


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by W. B. Barr under GLO contract dated September 10, 1880.

Surveyor's General records state: "Marked basalt rock 15 x 10 x 6. Raised a mound of rocks as per instructions.




Description of corner evidence found:

See the attached narrative for documentary evidence and comments.

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2½-inch brass cap on a 1-inch iron pipe, 26-inches in the ground, with surrounding rock mound.

Brass cap is marked thus:



CS 1980

New bearing trees:

A pine 21 ins. diam bears N 48° E, 153.2 ft. dist. mkd. T 8 S R 43 E S 3 BT. A pine 15 ins. diam bears S 02° E, 148.7 ft. dist. mkd. T 8 S R 43 E S 10 BT. A pine 14 ins. diam bears S 26° W 95.3 ft. dist. mkd. T 8 S R 43 S 9 BT. A pine 22 ins. diam bears N 01° W, 381.1 ft. dist. mkd. T 8 S R 43 E S 4 BT.

I hereby certify that the above corner monument was properly remonumented under my supervision Sept. 8, 1980, witnessed by Brad Gordon, Tom Fisk, and Jim DeMastus. Co. Surv. County of Baker

State of Oregon, I hereby certify that the within Instrument was filed in this office for record on the 11 day of Sept., 1980.

James D. Hanley
(COUNTY OFFICIAL)

(DEPUTY)

FILED 9-11-80
BAKER COUNTY SURVEYOR
SURVEY NO. 8-43-10

