


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by W. Barr, under contract no. 372, dated 1880.

Marked basalt rock 15" x 8" x 6". Dug pits.



Description of corner evidence found:

Found no evidence of original stone or pits. Accepted fence corner as best possible evidence of corner location.

See narrative accompanying plat of Sections 2 and 3, T. 7 and 8 S. R. 43 E.W.M.

Description of monument and accessories established to perpetuate the original location of this corner: Set 2 1/2" x 30" aluminum pipe with 3 1/4" aluminum cap 24" in ground in mound of stone. Marked:

Bearing Tree

20" ponderosa pine, S 74° E, 150.0 ft., scribed "T8S R43E S12" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

Reference Mounds

- 3 ft. x 3 ft. mound of stone, S 51° W, 3.0 ft.
- 4 ft. x 3 ft. mound of stone, N 49° W, 6.4 ft.
- 3 ft. x 3 ft. mound of stone, N 29° E, 3.0 ft.

Compass declination 20° East

Note:

I set guard posts at corner with USFS 54-2 and 54-4 signs, placed 54-3 and 54-4 signs on bearing tree and painted a red band at breast height on smoothed bark, and placed USFS 54-3 and 54-4 signs on reference mounds.

I hereby certify the above corner location was perpetuated as herein described on May 31, 1982.

Terry Butler Terry Butler, Witness

Frank Vaughn Frank Vaughn, Witness

REGISTERED PROFESSIONAL LAND SURVEYOR
---

*Carl E. Sundet*

OREGON JULY 14, 1978 CARL E. SUNDET 1664
---

Office of..... County of.....  
 State of..... I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)