


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by W. Barr, under contract no. 372, dated 1880.

Marked basalt rock 16" x 14" x 4". Raised mound of rock.



Description of corner evidence found:

Found a 16" x 14" x 4" stone notched on east and west edges.

Description of monument and accessories I established to perpetuate the

original location of this corner: Set a 2 1/2" x 30" aluminum pipe with a 3/4" aluminum cap 21" in ground in mound of stone. Buried original stone alongside new monument. Cap marked;


Bearing Trees

14" ponderosa pine, N 74° W, 58.6 ft., scribed "T7S R43E S34" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

13" ponderosa pine, N 02° E, 84.2 ft., scribed "T7S R43E S35" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

15" ponderosa pine, S 50° W, 34.1 ft., scribed "T8S R43E S3" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

9" ponderosa pine, S 66° E, 61.5 ft., scribed "T8S R43E S2" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.



Compass declination 20° East

Note:

I set a guard post at corner with USFS 54-4 sign, and placed USFS 54-3 and 54-4 signs and painted a red band on smoothed bark at breast height on bearing trees.

I hereby certify the above corner location was perpetuated as herein described on June 3, 1982.

Terry Butler Terry Butler, Witness

Frank Vaughn Frank Vaughn, Witness

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet
OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Office of..... County of.....

State of.....; I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED June 29, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 7-43-55
8-43-22

☆ GPO—798-276