

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None

DIAGRAM

T8S R43E

S1/16

S2 | S1

Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" x 30" aluminum pipe with 3/4" aluminum cap 14" in ground, to bedrock, in large mound of stone, marked:



Bearing tree:

29" douglas fir - N60°E - 106.5 ft. scribed "S1/16 S1" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze

Accessory:


3' x 3' mound of stone - N55.5°W - 9.9 ft.

Compass declination 20.75° East


Note:

I set steel fence post 5' north of corner with USFS 54-9 sign, painted red band on smoothed bark at breast height on bearing tree. Placed USFS bearing tree signs and 54-9 signs on bearing tree and accessory.

I hereby certify the above corner was perpetuated as herein described in November 1982



Office of..... County of..... State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of..... 19.....



(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED Dec 20 1982

BAKER COUNTY SURVEYOR

SURVEY NO. 8-43-31

GPO-798-276