

Corner Monumentation in Sections 2 and 3, T. 8 S. R. 43 E. W.M. Baker County, Oregon

Forshey Cadastral Survey

① Fd : 24"x10"x10" stone scribed 1/4 in mos.
Set : AP 12" in ground in mos. Buried original stone alongside new monument. Comp. decl. 20.75° East
Ref: 4ft. x 2ft. m.o.s. S 6°W - 7.0 ft.
5ft. x 2ft. m.o.s. East - 5.0 ft.

② Fd : No evidence of original stone. Set by proportionate measurement.
Set: AP 20" in ground in mound of stone. Comp. decl. 20° East
Ref: 3 1/2' x 4' m.o.s. N 25°W - 8.7'
3 1/2' x 3 1/2' m.o.s. N 31°E - 7.4'
3 1/2' x 3 1/2' m.o.s. S 34°W - 10.0'
3' x 3' m.o.s. S 29°E - 9.5'

③ Fd : 12"x10"x8" stone with 1/4 scribed on north face and in a mos.
Set: AP 24" in ground in mos. Buried original stone alongside new monument. Comp. decl. 20° East
Ref: 13" PPBT. N 69°W - 82.9 ft.
15" PPBT. S 22°E - 118.8 ft.

④ Fd : 16"x14"x4" stone notched on east and west edges.
Set: AP 21" in ground in mos. Buried original stone alongside new monument. Comp. decl. 20° East.
Ref: 14" PPBT. N 74°W - 58.6 ft.
13" PPBT. N 02°E - 84.2 ft.
15" PPBT. S 50°W - 34.1 ft.
9" PPBT. S 66°E - 61.5 ft.

⑤ Fd : No evidence of original stone. Set by proportionate measurement.
Set: AP 21" in ground in mos. Comp. decl. 20° East.
Ref: 3 ft. x 3 ft. m.o.s. N 13°E - 6.2 ft.
3 ft. x 3 ft. m.o.s. S 06°E - 7.3 ft.

⑥ Fd : Weathered cinder stone in fence corner. No scribing visible.
1 1/2" iron pipe at fence corner.
Ref: PPBT. N 27°E - 4.92 ch. as per 1919 survey. B.T. is dead and down.
Set: AP 15" in ground in mos. Comp. decl. 20° East.
Ref: 3ft. x 2 1/2 ft. m.o.s. N 54°W - 7.4 ft.
3ft. x 3ft. m.o.s. N 56°E - 8.4 ft.
3ft. x 3ft. m.o.s. S 46°W - 8.9 ft.
3ft. x 3ft. m.o.s. S 36°E - 11.4 ft.

⑦ Fd : No evidence of original stone or pits. Accepted fence corner as best possible evidence of corner location. See accompanying narrative.
Set: AP 24" in ground in mos. Comp. decl. 20° East.
Ref: 20" PPBT. S 74°E - 150.00 ft.
3ft. x 3ft. m.o.s. S 51°W - 3.0 ft.
4ft. x 3ft. m.o.s. N 49°W - 6.4 ft.
3ft. x 3ft. m.o.s. N 29°E - 3.0 ft.

⑧ Fd : 15"x10"x6" stone with 1/4 scribed on north face in a mos. Buried it alongside new monument.
Set: AP 6" in ground in mos. Comp. decl. 20° East.
Ref: 4ft. x 4ft. m.o.s. north - 9.5 ft.
4ft. x 3ft. m.o.s. south - 7.0 ft.

⑨ Fd : No evidence of original stone.
36" PPBT. dead and down, S 50°E - 63 lks (S 50°E - 63 lks)
Scribing visible but badly weathered and unreadable.
18" PPBT. alive with healed face, N 43°E - 77 lks (N 43°E - 72 lks). This BT set by Drake in 1919.
"X" chiseled on rock, N 44°W - 23 lks (N 34°W - 23 lks)
This done by Drake in 1919.
Set: AP 21" in ground in mos. Comp. decl. 20° East.
Ref: 11" PPBT. S 20°E - 23.5 ft.
6" PPBT. S 25°W - 32.0 ft.
9" PPBT. N 61°W - 63.6 ft.

⑩ Fd : No evidence of original stone. Set by proportionate measurement.
Set: AP 24" in ground in mos. Comp. decl. 20° East.
Ref: 27" PPBT. N 48°E - 189.2 ft.
4ft. x 4ft. m.o.s. S 14°W - 14.0 ft.

⑪ Fd : 2 1/2" G.I. Pipe with 2 1/2" brass cap in m.o.s.
Ref: 22" PPBT. N 01°W 381.66 ft.
22" PPBT. N 51°E 153.33 ft.
16" PPBT. S 84°E 148.82 ft.
15" PPBT. S 34°W 95.20 ft.

⑫ Fd : No evidence of original stone. Set by proportionate measurement.
Set: AP 22" in ground in mos. Comp. decl. 20.75° East
Ref: 3ft. x 1 1/2 ft. m.o.s. S 19°W 11.6 ft.
3ft. x 1 1/2 ft. m.o.s. S 51°E 11.3 ft.

⑬ Set: AP 12" in ground in m.o.s. Comp. decl. 20.75° East
Ref: 3 1/2 ft. x 2 ft. m.o.s. S 85°W - 8.0 ft.
3 ft. x 2 1/2 ft. m.o.s. S 54 1/2°E - 6.0 ft.

⑭ Fd : No evidence of original stone. Set by proportionate measurement
Set: AP 26" in ground in m.o.s. Comp. decl. 20.75° East
Ref: 11" PPBT. N 69°W - 31.1 ft.
22" DF.B.T. N 40°E - 15.3 ft.

⑮ Set: AP 14" in ground in m.o.s. Comp. decl. 20.75° East
Ref: 3 ft. x 3 ft. m.o.s. N 55 1/2°W - 9.9 ft.
29" DF.B.T. N 60°E - 106.5 ft.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet
OREGON
JULY 14, 1978
CARL E. SUNDET
1664

FILED Dec. 20, 1982

BAKER COUNTY SURVEYOR
SURVEY NO. 8-43-34

Surveyed for: US Forest Service
Contract no. 53-04M3-1-2667N
Surveyed by: SUNDET AND ASSOCIATES
PO Box 1228
Lakeview, Oregon
Ph.No. 503-947-3293

Date: 1981-1982
Drawing No. 1214 B

Sheet 2 of 2

8-43-34