

# SUNDET & ASSOCIATES

LAND SURVEYING

LAKEVIEW, OREGON 97630

PHONE 947-3293

P.O. Box 1228

November 26, 1982

## SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

Survey for: Wallowa-Whitman National Forest  
P.O. Box 907  
Baker, Oregon 97814

Location: Located in sections 2 & 3, T.8S. R.43E., W.M.,  
Baker County, Oregon

Purpose: Monumentation of corners and marking of the  
property line between private and Forest Ser-  
vice ownership.

Date: Survey completed November 1982

Procedure: Survey began with the search for original corners. The section corner to sections 3, 4, 9 & 10 was found to have been monumented by the Baker County Surveyor. Original corners found were:  $\frac{1}{4}$  33 & 4,  $\frac{1}{4}$  34 & 3, section corner 2, 3, 34 & 35, section corner 2, 3, 10 & 11, and the  $\frac{1}{4}$  2 & 11. Corners set by proportionate measurement were 3, 4, 33 & 34,  $\frac{1}{4}$  2 & 35,  $\frac{1}{4}$  3 & 10,  $\frac{1}{4}$  3 & 4, and the  $\frac{1}{4}$  1 & 2. The exterior boundaries of sections 2 & 3 were resurveyed by George Drake, Forest Examiner, in 1919, the field notes of which are on file with the Wallowa-Whitman National Forest office in Baker, Oregon. Drake is very clear in his notes as to the original corners he found, additionally he set large mounds of stones on the property lines with posts and the old style forest boundary signs. It also appears that fences were built soon after his survey following the mounds and posts that he set. Drake found the section corner to sections 1, 2, 35 & 36 and perpetuated it by establishing a bearing tree. At the assumed corner location we found a weathered cinder stone marked with an "X" on top and a  $1\frac{1}{2}$ " galvanized iron pipe next to a fence corner, from which the rotted remains of a scribed bearing tree is at the location described by Drake. This location

FILED Dec 20 1982

BAKER COUNTY SURVEYOR

SURVEY NO. 8-43-35