

was accepted as the best evidence of the original corner location.

At the location of the section corner 1, 2, 11 & 12 no original evidence was found. Drake states that he found this stone in 1919. I accepted as the best evidence of this corner a fence corner, with fences running north, south and west, said point also being the intersection of the mounds north and west marking the line established by Drake.

It appears by comparing distances and bearings to the original, that the original survey was not closed on the township line or that erroneous calls were returned to the Surveyor General. The  $\frac{1}{4}$  corners 1 & 2 and 3 & 4 were searched at 40 chains in each direction from the controlling section corners and at the proportionate distance. No original evidence could be found. We also searched for the  $\frac{1}{4}$  corners 2 & 3 and 4 & 5 without success to try and establish a pattern of the original survey. Due to complete lack of evidence of any of these  $\frac{1}{4}$  corners the positions of the  $\frac{1}{4}$  corners 1 & 2 and 3 & 4 were established by proportionate measurement. It should be noted that there are old fences in the area of these corners and that the stones may have been incorporated into numerous fence jacks. Also these corners were not found by Drake in 1919 when we assume the corner vicinity to have been in a much less disturbed condition.

Additional corners set by proportionate measurement were the S1/16 1 & 2 and the N1/16 3 & 4.

Property lines were marked with steel fence posts and Forest Service property boundary signs.

Instruments used were Jena one-second theodolite and Mac I-H electronic distance measuring device.

This narrative of survey accompanies and is hereby made a part of the Record of Survey.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Carl E. Sundet*

OREGON  
JULY 14, 1978  
CARL E. SUNDET  
1664